Flansburgh Architects



2017 – 2018 Elementary School Study

Agenda

Welcome and Opening Comments

Dr. Mary Malone, Superintendent

Current State of Elementary Schools

Mr. Jorge Cruz, Flansburgh Architects

. Working with the Massachusetts School Building Authority (MSBA)

Mr. Dan Gleason and Mr. Jonathan Deforge, ASRSD School Committee

21st Century School Building Concepts

Mr. Jorge Cruz, Flansburgh Architects

Next Steps

Mr. Dan Gleason and Mr. Jonathan Deforge, ASRSD School Committee

. Q&A



Current State of Elementary Schools

- The schools are serviceable and have no safety concerns to continue operation.
- The systems are exceeding their expected service lives and need to be replaced or upgraded.
- The schools are not energy efficient and upgrades to systems should include energy savings equipment and materials.
- Capital expenditures will be required and code thresholds need to be considered in a repair plan.
- There are no code implications that require significant changes to the existing schools.
- Enrollment forecast for the next ten years is flat with roughly 825 total students in grades K-5 annually.
- Final report includes identification of the potential and suggested capital improvements necessary to extend the useful life of each facility.



What is the MSBA?

- Massachusetts School Building Authority A quasi-independent state government agency under the Treasurer's Office tasked with funding capital improvements in Massachusetts public schools.
- . How is the MSBA Funded? One penny of each 6.25 cents of sales tax.
- Since it was established in 2004, the MSBA has made more than \$13 billion in reimbursements to cities, towns, and regional school districts.
- . The MSBA has participated in, or is currently working on, over 600 projects.



MSBA Programs

Core

- Major construction, either addition/renovation or new building.
- High school addition/renovation was funded through this program.

Repairs

- Major Major repairs on a facility otherwise capable of supporting the educational program. Follows the Core program processes and timelines.
- Accelerated Generally roofs, windows, and boilers. An accelerated project plan no more than 18 months in length.
 - Accelerated Repair funds are pro rated if later a Core project is approved
 - For example, if you replace windows, but five years later build a replacement school, reimbursement for the new school will be reduced by a percentage of cost of the windows.



Why Work With MSBA?

- Millions of dollars of reimbursements, which saves local taxpayers in what otherwise would have to be larger property tax increases via debt exclusion.
 - Base rate begins at 31%, increases based on community demographics and other incentives.
 - New Harvard elementary school: 35%; Crocker elementary Fitchburg: 80%
 - Ayer Shirley HS addition / renovation: 70%
 - Basis for later slides in this presentation: 50%
- Returns your sales tax dollars to your community.
- A proven process encompassing all phases of a project Feasibility, Design,
 Construction.
- Access to vetted and high quality architects, owner's project managers (OPM), and construction management companies.



MSBA Project Considerations


- The process is long, complex, and cumbersome.
- MSBA only accept Statements of Interest (SOI) once per year.
- Getting accepted into their program is a competitive process and only so many school projects get accepted per year.
 - · Projects are scored against the cohort of applications on a yearly basis.
 - In 2017, the MSBA received 83 SOI's from 59 different school districts.



Sample Elementary School Project Timeline

Durations are represented as "Best Case" and tend to be longer.	Jan	Apr	ja ,	t o	Jan	Apr	od to	Jan	Apr	٦	oct	Jan	Apr	ā (t o	Jan	Apr	od bo	Jan	Apr	크	od	Jan	Apr	Inf	od	Jan	Apr	od od	Jan	Apr	рг	od
MSBA PROCESS		201	18	0	- 83	2019			20	20			202	ı İ	88	- 1	2022			20	023			20	24			2025	5		20	26	
Fund study; generate and submit SOI to MSBA																																	
MSBA Review																																	
MSBA Module 1: Eligibiliy Period (if selected)																																	
MSBA Module 2: Project Team Formation																																	
MSBA Module 3: Feasibility Study																																	
MSBA Module 4: Schematic Design																																	
MSBA Module 5: Project Scope and Funding																			(C)														
MSBA Module 6: Documentation and Bidding																							0										
MSBA Module 7: Construction																																	
Furniture, Fixtures, Equipment & Move In																																	
School Opens for Occupancy																												7	4				
MSBA Module 8: Closeout Finances																																	

Ayer Shirley High School Actual Time Line



Page Hilltop Elementary

Space Program at Page Hilltop Elementary


ACUTAL VS. MASSACHUSETTS SCHOOL BUILDING AUTHORITY (MSBA) GUIDELINES

Page Hilltop Elementary School at 522 Students	Existing C	onditions	MSBA Guidelines			
Room Type	# of Rooms	Area Totals	# of Rooms	Area Totals		
Core Academic Spaces	45	34,875	23	22,850		
Special Education	(include	d above)	12	6,040		
Art & Music	4	3,800	8	325		
Health & Physical Education	3	6,928	3	6,300		
Media Center	8	5,395	1	3,019		
Dining & Food Service	14	11,100	5	7,341		
Medical	2	523	5	650		
Administrative & Guidance	11	5,447	12	2,387		
Custodial & Maintenance	0	0	7	2,122		
Other—District Offices	7	2,284	0	0		
Proposed Student Capacity/Enrollment				522		
Total Building Gross Floor Area (GFA) ²		110,000		80,440		

Page Hilltop Elementary School Site Plan Option 1 - Renovation



Page Hilltop Elementary School Floor Plan Option 1 - Renovation




Page Hilltop Elementary School Site Plan

Option 2 – Renovation / Addition




Page Hilltop Elementary School Floor Plan Option 2 – Renovation / Addition




OPTION 2	EXISTING SF. 110,000
ADDITION / RENOVATION	NEW SF. 81,000
# STORIES	2
# CLASSROOMS	35
PROPOSED ENROLLMENT	522

Page Hilltop Elementary School Site Plan Option 3 – New Construction




Page Hilltop Elementary School Floor Plan Option 3 – New Construction





FIRST FLOOR PLAN

OPTION 3	
NEW SCHOOL	NEW SF. 87,000
# STORIES	2
# CLASSROOMS	35
PROPOSED ENROLLMENT	600



SECOND FLOOR

SPACE SUMMARY LEGEND

Lura A. White Elementary

Space Program at Lura A. White Elementary


ACUTAL VS. MASSACHUSETTS SCHOOL BUILDING AUTHORITY (MSBA) GUIDELINES

Lura A. White Elementary School at 378 Students	Existing C	Conditions	MSBA Guidelines			
Room Type	# of Rooms	Area Totals	# of Rooms	Area Totals		
Core Academic Spaces	30	25,638	16	15,950		
Special Education	4	1,202	9	4,530		
Art & Music		d above)	6	2,575		
Health & Physical Education	10	8,038	3	6,300		
Media Center	3	2,428	1	2,371		
Dining & Food Service	2	4,065	5	6,039		
Medical	1	272	4	510		
Administrative & Guidance	6	1,760	11	2,093		
Custodial & Maintenance	0	0	6	1,978		
Other—General Purpose Room/Storage	0	0	0	(
Proposed Student Capacity/Enrollment				379		
Total Building Gross Floor Area (GFA) ²		65,836		64,600		

Lura A. White Elementary School Site Plan Option 1 - Renovation



Lura A. White Elementary School Floor Plan Option 1 - Renovation




OPTION 1	
RENOVATION	EXISTING SF. 66,047
# STORIES	2
# CLASSROOMS	25
PROPOSED ENROLLMENT	378

Lura A. White Elementary School Site Plan Option 2 – Renovation / Addition



Lura A. White Elementary School Floor Plan Option 2 – Renovation / Addition




OPTION 2	EXISTING SF. 66,04
ADDITION/RENOVATION	NEW SF. 64,600
# STORIES	
# CLASSROOMS	2:
PROPOSED ENROLLMENT	37


Lura A. White Elementary School Site Plan Option 3 – New Construction



Lura A. White Elementary School Floor Plan Option 3 – New Construction








FIRST FLOOR PLAN

SECOND FLOOR PLAN


OPTION 3	
NEW SCHOOL	NEW SF. 68,000
# STORIES	2
# CLASSROOMS	25
PROPOSED ENROLLMENT	400

Regional Elementary School

Regional Elementary School Site Plan



Regional Elementary School Floor Plan



STORIES # CLASSROOMS

PROPOSED ENROLLMENT

50

900

Projected Budgets for Elementary School Options

Page Hilltop Elementary School Options

Option 1—Renovation	
Probable Construction Cost	\$42,852,000
Soft Cost @ 30%	\$12,855,600
Projected Total Budget	\$55,707,600
Option 2—Renovation/Addition	
Option 2 Renovation/Addition	7
Probable Construction Cost	\$38,169,500
Soft Cost @ 30%	\$11,450,800
Projected Total Budget	\$49,620,300
Option 3—New Construction	
Probable Construction Cost	\$42,217,400
Soft Cost @ 30%	\$12,665,200
Projected Total Budget	\$54,872,600

Lura A. White Elementary School Options

Option 1—Renovation	
Probable Construction Cost	\$25,258,400
Soft Cost @ 30%	\$7,577,500
Projected Total Budget	\$32,835,900
Option 2—Renovation/Addition	
Probable Construction Cost	\$31,636,300
Soft Cost @ 30%	\$9,490,900
Projected Total Budget	\$40,127,200
Option 3—New Construction	
Probable Construction Cost	\$34,568,100
Soft Cost @ 30%	\$10,370,400
Projected Total Budget	\$44,938,500

Regional Elementary School

Projected Total Budget	\$78,605,800
Soft Cost @ 30%	\$18,139,800
Probable Construction Cost	\$60,466,000
New Construction	i

Renovations vs. New School Cost Analysis

New Regional Elementary School @ 50% District Share	\$39,302,900
Total District Cost	\$49,905,550 — — — —
New School (Option 3) at Lura A. White @ 50% District Share	\$22,469,200
New School (Option 3) at Page Hilltop @ 50% District Share	\$27,436,300
Total District Cost	\$88,543,500
Renovation (Option 1) at Lura A. White @ 100% District Share	\$32,835,900
Renovation (Option 1) at Page Hilltop @ 100% District Share	\$55,700,600

Next Steps

- Summer / Fall 2018: Administration reviews recommended repairs and recommends plan to school committee within time and budget constraints.
- Fall 2018 (tentative): Prepare MSBA Statement of Interest (SOI).
- Early 2019 (tentative): Submit SOI to MSBA.
- Fall 2019 Response from MSBA
 - If successful, request funds from towns for Feasibility Study phase.
 - If unsuccessful, work with MSBA to understand why and resubmit SOI in 2020.



Q & A

Thank you for attending.

